

**BID FORM  
POPLAR SPRINGS BALL FIELDS  
MATERIALS & LABOR TO BUILD RESTROOM FACILITY**

Item No.	Item	Description	Quantity	Unit	Unit Cost	Total Cost
1	Surveying	Item shall include construction surveying and grade staking and elevation.	1	LS		
2	Permits	Building, Sewer, Water, and other fees & permits as required	1	LS		
3	Tap Fees	Water, Sewer, Electrical	1	LS		
4	Sewer	Trench and tie-in approx 600' to to existing sewer	1	FT		
5	Sewer	Grinder Pump (acceptable to City of Ringgold Spec)	1	LS		
6	Water	Approx 50' to tie into existing water and have individual cut off.	1	FT		
7	Excavating & Finish Grade	Excavate and finish grade up to building	1	LS		
8	Pour & Set Footings	Pour and set footings for building	1	LS		
9	Block	Split-faced block façade around all walls to match gym color	1	LS		
10	Siding	Vinyl for soffits and interior ceilings	1	LS		
11	Electrical (lights, dryers and fans)	8 ( 4' industrial grade recessed flourescent lights) & 2 exhaust fans (fans to be tied into the light switch), 2 hand dryers	1	LS		
12	Electrical (main facility and outlets)	connect restroom facility to main, and 4 electrical outlets (2 inside and 2 outside, 1 set for each bathroom)	1	LS		
13	Plumbing (sinks, toilets, urinals)	4 sinks (industrial stainless steel), 6 toilets, 2 urinals (all auto-flush)	1	LS		
14	Roof	4/12 Hip Style Metal Roof, 16" O.C. w/ 24" overhang w/ 7/16" OSB decking w/ provided underlayment by customer	1	LS		
15	Garage Door/Walk in door.	9' Roll Up Garage Door, 1 - 3' steel entry way door w/ push pad exit and pull handle entry on field side of building	1	LS		
16	Bathroom Doors	3' steel entry way doors w/ push pad exit and handle entry on gym side of building	2	EA		
17	Bathroom Stalls	8" x 16" block stall dividers. Handicap stall in each bathroom compliant to code requirements size and equipment.	1	LS		
18	Floor	Bathroom floors to slope to middle of floor to drain to tie into sewer	1	LS		
19	Bathroom support items	4 hand dryers, 4 mirrors and 6 multi-roll toilet paper dispensers. (all industrial grade )	1	LS		
20	Flood Vents	Provide & Install suffecient flood vents that comply with Flood Damage Prevention Ordinance of Catoosa Coutny	1	LS		

**TOTAL LUMP SUM COST** \_\_\_\_\_

Note:

- 1 This Project shall be paid as a Lump Sum. The Contractor shall provide Unit Costs per the Units requested on this form and these unit rates will be used as Unit Pricing should the scope increase or decrease.
- 2 Facility may be bid as pre-fab, turn-key unit as long as it meets all individual requirements as listed above.
- 3 Contractor shall be responsible for performing his own quantity take off.
- 4 Structure is located in floodplain. No-Rise Certificate to be furnished to city of Ringgold by RYAA Surveyor/Engineer.

**Company:** \_\_\_\_\_

**Signature:** \_\_\_\_\_

**Name:** \_\_\_\_\_

**Title:** \_\_\_\_\_

**Date:** \_\_\_\_\_

**BID FORM ATTACHMENT CHECKLIST:**

- Signed Addenda (if applicable)
- Copy of Contractors License
- Certificate of Insurance
- Schedule